

AD-A144 788


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
COLUMBIA LAKE DAM (CT...U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV SEP 78


1/2

UNCLASSIFIED

F/G 13/13

NI





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS - 1963-A

**THAMES RIVER BASIN  
COLUMBIA, CONNECTICUT**

**AD-A144 768**

**COLUMBIA LAKE DAM  
CT 00520**

**PHASE 1. INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM**

**DTIC FILE COPY**

This document has been approved  
for public release and sale; its  
distribution is unlimited.



**DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS.**

**SEPTEMBER 1978**

**04 08 20 022**

**DTIC  
ELECTE**

**AUG 23 1984**

**A**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE  |  | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM                 |
|--|--|---|
| 1. REPORT NUMBER<br><br>CT 00520   | 2. GOVT ACCESSION NO.<br><br>ADP-44765 | 3. RECIPIENT'S CATALOG NUMBER                               |
| 4. TITLE (and Subtitle)<br><br>Columbia Lake Dam   |  | 5. TYPE OF REPORT & PERIOD COVERED<br><br>INSPECTION REPORT |
| NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  |  | 6. PERFORMING ORG. REPORT NUMBER                            |
| 7. AUTHOR(s)<br><br>U.S. ARMY CORPS OF ENGINEERS<br>NEW ENGLAND DIVISION   |  | 8. CONTRACT OR GRANT NUMBER(s)                              |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS  |  | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>DEPT. OF THE ARMY, CORPS OF ENGINEERS<br>NEW ENGLAND DIVISION, NEDED<br>424 TRAPELO ROAD, WALTHAM, MA. 02254  |  | 12. REPORT DATE<br><br>September 1978                       |
|  |  | 13. NUMBER OF PAGES<br><br>90                               |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)  |  | 15. SECURITY CLASS. (of this report)<br><br>UNCLASSIFIED    |
|  |  | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE                  |
| 16. DISTRIBUTION STATEMENT (of this Report)<br><br>APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED   |  |   |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)   |  |   |
| 18. SUPPLEMENTARY NOTES<br>Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.   |  |   |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br><br>DAMS, INSPECTION, DAM SAFETY,<br><br>Thames River Basin<br>Columbia, Connecticut   |  |   |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br>Columbia Lake Dam is an earth dam which is approximately 295.0 ft. long (including spillway) and has a maximum height of 28.0 ft. The dam is considered to be in poor condition. A spillway design test flood outflow of 1418 cfs ( $\frac{1}{2}$ the PMF) will overtop the dam by approximately 0.93 ft. |  |   |

COLUMBIA LAKE DAM

CT 00520

THAMES RIVER BASIN  
COLUMBIA, CONNECTICUT

PHASE 1 INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

SEARCHED  
SERIALIZED  
AUG 23 1984

A



AI

This document has been approved  
for public release and sale; its  
distribution is unlimited.

NATIONAL DAM INSPECTION PROGRAM

PHASE 1 INSPECTION REPORT

Identification No.: CT 00520  
Name of Dam: Columbia Lake Dam  
Town: Columbia  
County and State: Tolland County, Connecticut  
Stream: Unnamed Stream  
Date of Inspection: 18 May, 1978

BRIEF ASSESSMENT

Columbia Lake Dam is an earth dam which was constructed in 1865. The dam has a maximum height of 28.0 ft. and is approximately 295.0 ft. long (including spillway). The embankment slopes are approximately 2.5 H : 1.0 V. The crest and downstream slope are grassed and the upstream face is riprapped above water level and to a depth of 3.0 ft. below water surface. The spillway is located on the extreme left abutment of the embankment and is a curved converging type contained between vertical rubble masonry walls. It is 26.0 ft. wide by 260.0 ft. long with a rubble stone bed that was filled with dumped concrete. The spillway flows discharge into a narrow natural stream bed leading to a 6.0 ft. x 4.5 ft. concrete box culvert beneath

Route 87 immediately downstream from the dam. There are no plans, specifications or computations available from the Owner, County or State offices regarding the design, construction or repairs of this dam.

Due to its age, Columbia Lake Dam was neither designed nor constructed by approved state of the art methods. Based upon the visual inspection at the site, the lack of engineering data available, and no operational or maintenance evidence, there are areas of concern which must be corrected to assure the long term performance of this dam. Therefore, based on existing information, this dam is considered to be in poor condition.

There are several visible signs of distress which indicate a potential hazard at this site: undermining and erosion beneath the spillway bed, deterioration of the outlet gate to the point where its operation is difficult and unreliable, erosion holes adjacent to the operating mechanism which may indicate leakage or seepage along the outlet conduit, emerging seepage along the downstream toe of the dam, dislodged stonework and obstructed downstream spillway channel and a general lack of proper, regular maintenance.

Hydraulic analyses indicate that the existing spillway can discharge a maximum flow of 624.0 cfs at Elev. 502.0 (top of Dam). A spillway design test flood outflow of 1418 cfs (one-half of the probable maximum flood) will overtop the dam by approximately 0.93 ft. Due to the potential for overtopping, it is recommended that a definite plan for surveillance and a warning system be developed for use during periods of unusually heavy rains and runoff.

It is recommended that the Owner immediately engage the services of an engineer experienced in the design of dams to accomplish the following: develop and implement a program of redesign for the dam to provide adequate spillway capacity, freeboard, riprap protection, and outlet works capacity using current hydrologic criteria; institute repair and/or rehabilitation of the present outlet works gate in order that control of the water be maintained; examine the present seepage and surface erosion holes and design a system for collection of the flow and monitoring; initiate short term repairs to the spillway; develop and implement procedures to remove the rotting stumps and roots on the dam slopes; and institute a limited subsurface boring and testing program to accomplish the above. It is recommended




that the Owner also begin a regular program of inspection and maintenance including a plan of action for emergency situations.

The above recommendations should be implemented within 180 days after receipt of the Phase 1 Inspection Report. The alternative to these recommendations would be to drain Columbia Lake and maintain the water surface at a reduced level.

C-E MAGUIRE, INC.

by

*Richard W. Long*  
Richard W. Long, P.E.  
Vice President



This Phase I Inspection Report on the Columbia Lake Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman  
Chief, Foundation and Materials Branch  
Engineering Division




FRED J. RAVENS, Jr., Member  
Chief, Design Branch  
Engineering Division



SAUL COOPER, Member  
Chief, Water Control Branch  
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR  
Chief, Engineering Division

SEP 29 1978

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.


Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## TABLE OF CONTENTS


|                                 | <u>Page</u> |
|---------------------------------|-------------|
| LETTER OF TRANSMITTAL           |             |
| BRIEF ASSESSMENT                | i           |
| REVIEW BOARD SIGNATURE SHEET    | v           |
| PREFACE                         | vi          |
| TABLE OF CONTENTS               | vii         |
| OVERVIEW PHOTO                  | ix          |
| LOCATION PLAN                   |             |
| REPORT                          |             |
| SECTION 1 - PROJECT INFORMATION |             |
| 1.1 General                     | 1           |
| 1.2 Description of Project      | 2           |
| 1.3 Pertinent Data              | 8           |
| SECTION 2 - ENGINEERING DATA    |             |
| 2.1 Design                      | 13          |
| 2.2 Construction Records        | 13          |
| 2.3 Operation Records           | 13          |
| 2.4 Evaluation of Data          | 13          |
| SECTION 3 - VISUAL INSPECTION   |             |
| 3.1 Findings                    | 14          |
| 3.2 Evaluation                  | 17          |

## TABLE OF CONTENTS

|   | <u>Page</u> |
|---|-------------|
| SECTION 4 - OPERATIONAL PROCEDURES                            |             |
| 4.1 Procedures  | 17          |
| 4.2 Maintenance of Dam  | 18          |
| 4.3 Maintenance of Operating Facilities                       | 19          |
| 4.4 Description of Any Warning System in Effect               | 19          |
| 4.5 Evaluation  | 20          |
| SECTION 5 - HYDRAULIC/HYDROLOGIC                              |             |
| 5.1 Evaluation of Features                                    | 20          |
| SECTION 6 - STRUCTURAL STABILITY                              |             |
| 6.1 Evaluation of Structural Stability                        | 24          |
| SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES |             |
| 7.1 Dam Assessment  | 27          |
| 7.2 Recommendations   | 31          |
| 7.3 Remedial Measures   | 32          |
| APPENDIX  |             |
| A Visual Inspection Check List                                |             |
| B Records, Inspection, Sketches, Drawings                     |             |
| C Selected Photos   |             |
| D Hydrologic Computations                                     |             |
| E Information as Contained in the National Inventory of Dams  |             |



C-1 COLUMBIA LAKE DAM - LOOKING SOUTH



PHASE I INSPECTION REPORT  
COLUMBIA LAKE DAM CT 00520

SECTION 1

PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. CE Maguire, Inc., has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed was issued to C-E Maguire, inc., under a letter of 26 April, 1978, from Ralph T. Garver, Colonel, Corps of Engineers Contract No. DACW33-78-C-0300 has been assigned by the Corps of Engineers for this work.

b. Purpose

- (1) Perform technical inspection and evaluation of non-Federal dams to identify conditions



which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) Encourage and assist the States to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 DESCRIPTION OF PROJECT:

a. Location: Columbia Lake is located in the She-tucket River watershed of the Thames River Basin, approximately 1.5 miles northwest of Columbia, Connecticut, in Tolland County. Columbia Lake has a surface area of approximately 270.0 acres, an average depth of 17.0 feet and a shoreline length of about 7.6 miles. The watershed of 3.1 square miles drains a rolling terrain which consists of swampland, woodland and farmland. The dam is located in the northwest corner of the lake parallel to, and approximately one hundred and eighty feet from, the highway embankment for Connecticut Route 87.

b. Description of Dam and Appurtenances: Based on visual inspection, the dam is an earth embankment

with a crest length of 295.0 feet (including spillway.) The upstream and downstream slopes are approximately 2.5 H : 1.0 V. The crest and the downstream slope are grassed. The upstream side is riprapped above water level and to a depth of at least 3.0 ft. below the water level. At the time of inspection, the water level was 1.1 feet below the crest.

The spillway is located on the extreme left side of the embankment and is a converging type contained between vertical rubble masonry walls. It is 26.0 feet wide by 260.0 feet long with a rubble stone bed that was filled with concrete. The right training wall is of grouted rubble and ranges from a height of 4.0 feet upstream to about 1.5 feet on the downstream side. The left training wall is of dry rubble construction with an average height of 9.0 feet. The spillway discharges from a rubble stone channel to a relatively small natural stream bed leading to a concrete box culvert 6.0 feet wide by 4.5 feet high under Route 87.

The intake gate for the outlet works is located on the outside face of a pier consisting of

vertical stone walls which have apparently been filled with earth. The pier is located to the right of center of the dam embankment, and it extends approximately 60.0 feet out into the lake. The gate is manually operated. The mechanical works are positioned on the extreme upstream end of the pier (see Photo C-6). The downstream end of the outlet is an 18-inch diameter cast iron pipe which discharges into a 40-inch wide by 16-inch high stone box culvert (see Photo C-7). The downstream channel is a natural streambed. It flows to the box culvert beneath Route 87 (see Photo C-8).

- c. Size Classification: The dam is classified as intermediate in size because the impoundment at crest elevation is 3370 Ac.-Ft. which exceeds 1000 Ac.-Ft., the limiting criteria for intermediate size.
- d. Hazard Classification: The dam is classified as a significant hazard potential because it is located in a predominantly rural or agricultural area where failure may damage isolated homes, secondary highways and some public utilities.

- e. Ownership: Town of Columbia, Connecticut. The dam was built around 1865 by the Willimantic Linen Company to augment their water supply. Ownership was transferred to the Willimantic Linen Company (now called the American Thread Company) in 1898 and in 1933 the title was transferred to the present owner.
- f. Gate Tender: Mr. Marshal Nuhfer  
Nuhfer Drive  
Columbia, Connecticut 06237  
(203)-228-3018
- g. Purpose of Dam: Columbia Lake is presently used solely for recreation.
- h. Design and Construction History: Columbia Lake is an entirely artificial body of water. In the early 1800's, a small millpond was built near the present outlet to provide water power for a sawmill. In 1865, the Lake as it appears today was created when the Willimantic Linen Company of Willimantic, Connecticut (now the American Thread Company) built the currently existing larger dam. For the next 68 years (until the water rights were purchased in October, 1933, by the Town of

Columbia) the lake was used as a back-up source of water power. As manufacturing in Columbia slowly declined, the importance of the lake as a recreational attraction steadily increased. In November, 1939 (as a result of the performance of the dam during the hurricane of September, 1938), following a directive from the State Board of Supervision of Dams for Connecticut, the dam was modified. The spillway was doubled in width from 13.0 feet to 26.0 feet and lined with "stone pavers." Records of that time also indicate that it was recommended that a 12-inch cut-off wall be installed beneath the spillway, penetrating 3.0 feet to 4.0 feet into hard material.

In April, 1963, it was recommended by a consultant to the State of Connecticut that all trees be removed from the embankment, debris cleared from the spillway, and an emergency spillway be excavated in natural ground at the right end of the embankment. An inspection of the dam in March, 1966, indicated that the trees and debris had been removed, but no emergency spillway had been excavated. In February, 1968, material was

added to the downstream slope above the toe wall and seeded. The top of the dam embankment was leveled, and an emergency spillway started. In August, 1968, the State of Connecticut, fearing possible overtopping of the dam based upon the performance of the dam during storms in March, 1968, directed that the emergency spillway be refilled to its former height.

Raising of the embankment 1.7 feet to provide additional freeboard, the addition of riprap on the upstream face, repairs to the spillway discharge and removal of trees and brush were recommended in September, 1971, by a consultant to the Water Resource Commission of the State. There were no observations made during visual inspection that would indicate that the dam has been raised subsequent to the 1971 recommendations. Therefore, the height of the dam now is apparently the same as in 1865.

- i. Normal Operational Procedures: Water surface levels in Columbia Lake are normally lowered approximately 6.0 to 8.0 feet around October 1 of each year, after the recreational season ends, to protect shoreline docks and piers from ice damage.

This reduced level is maintained until late spring when ice is no longer a problem. At this time, the gate is closed and the run-off collected for the next recreational season. Normal pool elevation is 498.0 NGVD (National Geodetic Vertical Datum).

1.3 PERTINENT DATA

- a. Drainage Area: The Columbia Lake drainage basin, located in eastern Connecticut, is generally elongated in shape and has a length of about 3.0 miles, an average width of 1.0 mile, and a total drainage area of 3.1 square miles. The topography is generally rolling hills with hilltops at Elevation 700+. Basin slopes are generally flat to moderate. A large swamp area (0.2 square miles) in the upper reaches of the watershed tends to dampen the effect of surface run-off from the steeper slopes of the wooded hillsides. A general basin map is enclosed, see Appendix D.
- b. Discharge at Dam Site: The largest storm experienced at the Columbia Lake Dam was the September, 1938 hurricane. Calculations prepared by the State of Connecticut in 1968 indicate that with the spillway 13.0 feet in width and the water level

approaching the top of the dam, the estimated discharge was 270 cfs during the 1938 hurricane. It is estimated that 960 cfs will flow into the reservoir due to a 100 year frequency storm event. This peak inflow rate is reduced by storage to produce an outflow of 132 cfs at the spillway, which is now 26.0 feet wide as computed by the Soil Conservation Service technique. The spillway design test flood (1/2 Probable Maximum Flood) as calculated in Appendix D is 3120 cfs and 1418 cfs as inflow and outflow, respectively based upon 1000 CSM as inflow value. Listed below are discharge data for spillway and outlet works:

1. Outlet works (conduit) size 18 inch diameter. Cast iron pipe with invert Elevation 471.0+
2. Maximum known flood at dam site 270 cfs in 1938.
3. Spillway capacity at maximum pool level (Elevation 502.0) - 624 cfs.
4. Gated outlet capacity at normal pool elevation with an open 18-inch diameter cast-iron pipe 73.0 cfs, with reservoir, at Elevation 498.0 and tail water at Elevation 471.0.



5. Gated outlet capacity at maximum pool level  
(Elevation 502.0) - 77 cfs.
  6. Total discharge (spillway and outlet) capacity at maximum pool level (Elevation 502.0) -  
701 cfs.
- c. Elevations: (feet above NGVD)
1. Top of Dam - Elevation 502.0
  2. Maximum pool-design surcharge - 4.0 feet  
with no freeboard
  3. Full flood control pool - Elevation 502.0  
with no freeboard
  4. Recreation pool - Elevation 498.0
  5. Spillway crest - Elevation 498.0
  6. Upstream invert of intake structure - Elevation 471.0 (estimated) - 27 feet ± below  
normal pool level
  7. Estimated elevations of streambed at center-  
line of dam upstream 471.0, downstream 470.0
  8. Maximum tailwater - not computed
- d. Reservoir Lengths: (feet)
1. Length of maximum pool - 5,600
  2. Length of recreational pool - 5,600
  3. Length of flood control pool - 5,600

e. Reservoir Storage: (acre-feet)

1. Recreation pool - 3,370 at Elevation 498.0
2. Flood control pool - 1,080 at Elevation 502.0
3. Surcharge - 1,080 between Elevation 498.0 and 502.0.
4. Top of dam - 4450 at Elevation 502.0.
5. Flood control pool of 1080.0 Ac.-Ft. represents 6.50 inches of runoff from the 3.12 Sq. Mi. Basin.

f. Reservoir Surface: (acres)

1. Top of dam - 270
2. Maximum pool - 270
3. Flood-control pool - 270
4. Recreational pool - 270
5. Spillway crest - 270
6. One foot of surcharge represents 1.62 inches of runoff from its drainage area of 3.12 Sq. Mile.

g. Dam

1. Type - Probably earth, because emergency spillway excavation was apparently made in earth and exposed surfaces are of earth.

2. Length - 295.0 feet (including spillway)
3. Height - 28.0 feet from streambed (downstream)
4. Top Width - 16.0 feet
5. Side slopes - 1 vertical on 2.5 horizontal  
(scaled)
6. Zoning - Unknown
7. Impervious Core - Unknown
8. Cut-off - Unknown. Correspondence indicates  
that a concrete cut-off 3 to 4 feet deep may  
exist beneath the spillway)
9. Grout curtain - Unknown
10. Other - Dry, cut-stone toe wall 6 to 10 feet  
high

h. Spillway

1. Type - Curved, converging, broad-crested,  
overflow spillway
2. Length of weir - 26.0 feet maximum normal to  
the flow converging to 16.0 feet
3. Crest elevation - Elevation 498.0
4. Gates - None
5. Upstream Channel - Straight, natural bed

i. Regulating outlet

1. Invert Elev. 471.0<sub>±</sub>
2. Size - 18" dia.
3. Description - Cast Iron Pipe
4. Control Mechanism-Manually operated vertical  
slide gate
5. Other - ---

SECTION 2  
ENGINEERING DATA

2.1 DESIGN

A topographic survey of the dam embankment conducted by T.A. Brindamour in June, 1968 is the only engineering data available. Elevations indicated on the topographic map resulting from this survey were not verified during this Phase I study.

2.2 CONSTRUCTION RECORDS

No data available.

2.3 OPERATION RECORDS

No data available.

2.4 EVALUATION OF DATA

- a. Availability - Limited to data mentioned in 2.1.
- b. Adequacy - Not adequate
- c. Validity - Not verified

SECTION 3  
VISUAL INSPECTION

3.1 FINDINGS

- a. General: At the time of the inspection, it appeared that the dam had recently been trimmed of brush and undergrowth and the downstream channel and terrain cleared. Fencing at the entrance to the access road and private property abutting the damsite has prevented surface erosion from trespass. It was observed that an attempt had been made in the past to repair the spillway bed using dumped concrete, but undermining of that slab is apparent. The masonry of the spillway training walls, particularly at the downstream ends, was dislodged and obstructing the bed of the spillway. Surface erosion holes in the crest of the outlet gate pier structure were observed. In general, it appeared that the condition of the dam was declining and not being properly maintained.
- b. Dam: Seepage at rates ranging up to several gallons per minute was observed emanating from the downstream side of the dam at locations indicated on Plate No. 3 and shown in Photographs Nos. C-5 and C-10.

Numerous stumps and, hence, rotting roots were present on the upstream and downstream slope. Photographs were taken of some stumps and appear in Photograph No. C-9.

An emergency spillway that was excavated on the dam crest, according to correspondence, appears to either have been incompletely backfilled or settled, as there is a definite low spot at present at that location.

The outside perimeter of the 18 inch diameter cast-iron-pipe outlet conduit at the base of the dam was wet, indicating that seepage may be occurring along its perimeter.

- c. Appurtenant Structures: Surface erosion holes up to 2.75 feet deep were found on the upstream end of the gate support structure. See Plate No. 3 for locations and Photograph No.C-11. Surface erosion holes were also found along the westerly spillway wall immediately west of the stonework. These are very likely due to loss of soil from openings between stones resulting from inadequate filter material between the stonework and the soil. The spillway was found to be seriously undermined and inadequate in size. Training

walls were collapsed and dislodged on the downstream discharge slope of the spillway.

The intake control of the outlet works was reportedly leaking severely, requiring alternate means to stop the leakage. These alternate means were reported to be dumped cinders adjacent to the gate.

- d. Reservoir Area: Gneiss bedrock was exposed 50 feet upstream from the right abutment of the dam embankment. At this location it is planar and dips at an angle of  $10^{\circ}$  in the direction N  $80^{\circ}$  W. A one-half inch wide nearly vertical joint in the rock is exposed. Its intersection with the horizontal plane strikes N  $50^{\circ}$  W, toward the highest part of the dam. The alignment of this joint with the main embankment intersects at a point which projected to the downstream toe lies near the seep area indicated on Plate No. 3 and could be the cause of that flow.
- e. Downstream Channel: The downstream channel is irregular and overgrown with trees. The bed of the channel is stained with a rust colored deposit. Several channels have been formed by the flowing water that emanates from the downstream

side of the dam. The beds of these channels are also rust-stained.

### 3.2 EVALUATION

Visual observation made during the course of the inspection did not indicate any conditions of an immediate critical nature. Several of the deficiencies observed and discussed above require attention and should be corrected before further deterioration develops a hazardous condition. Recommended measures are discussed in Section 7.

## SECTION 4

### OPERATIONAL PROCEDURES

#### 4.1 PROCEDURES

- a. Normal Operating Procedures: Columbia Lake is presently used primarily for recreational purposes. Regulation of the water level in the lake is synchronized with the summer boating and bathing season. Operation of the control outlet gate (which is always locked) is accomplished by a lake-front resident, Mr. Marshal Nuhfer, for the Town of Columbia. Generally, around the beginning of October the water level is lowered from Elevation 498.0 (Spillway Crest) approximately six to eight feet and held at that reduced level by



intermittent gate openings until the danger from ice damage to shorefront docks and piers has passed in the spring. Depending on the severity of the winter, the gates are closed on or about mid-March in order to raise the level back to its summer use stage. There are no other outlets to the impoundment.

- b. Emergency Operating Procedures: Impending intense rainfalls from approaching storms are monitored by the gate tender, the Town road foreman and the Selectmen through local radio or television forecasts or direct contact with the weather bureau. Keys to the control gate are held by the gate tender and the road foreman. No formal procedure exists for emergency situations. The necessary control is based on a judgment made by the keyholders or by the Selectmen. No records or graphs exist indicating past discharge or water levels.

#### 4.2 MAINTENANCE OF DAM

Maintenance of the dam has been neglected and has occurred generally only when directed by the State as a result of their inspections.

#### 4.3 MAINTENANCE OF OPERATING FACILITIES

Monitoring the need for maintenance of the gate control is generally the responsibility of the gate tender. The intake control mechanism is an aged mechanical structure exposed to weather and vandalism. Problems with closing the gate and leakage through the outlet pipe have been reported annually. Proposals for repairing the gate were requested by the Town in 1972, but no action was taken. On the downstream side, the outlet lies within the embankment toe and could be blocked or completely obstructed by the occurrence of a small slide or dislodgement of stones.

#### 4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

No formal warning system is used, but rather the gate operator, using public weather forecasts, judges the emergency and operates the gate accordingly. There is no pre-planned effective warning system for the failure of Columbia Lake Dam. An emergency action plan must be developed in order that operating personnel can notify authorities for mobilization of State and local emergency forces, organize remedial measures to minimize or prevent complete failures when possible and have an awareness of the locations of standby equipment and materials.

#### 4.5 EVALUATION

The dam and its appurtenances have been seriously neglected. There is no record of a formal program of inspection or maintenance conducted by the Owners nor is there a definitive contingency plan for emergency situations.

### SECTION 5

#### HYDRAULIC/HYDROLOGIC

##### 5.1 EVALUATION OF FEATURES

- a. Design Data: No specific design data is available. In lieu of existing design information, the U.S.G.S. topographic maps (Columbia Lake Quadrangle) were used to develop hydrologic parameters. Outflow for the Spillway Design Flood was developed using approximate routing parameters with the lake at spillway crest level (see Appendix D). Pertinent hydraulic design data was obtained and/or confirmed for the spillway, outlet and other appurtenant structures by actual field measurements. The dam failure profile was developed from the above mentioned topographic mapping. Surcharge storage was approximated assuming that the lake surface area remained constant above spillway crest elevation (as required by Corps) The results of the flood routing are as follows:

# INFLOW, OUTFLOW AND SURCHARGE DATA

| FREQUENCY<br>IN<br>YEARS | 24-HOUR TOTAL<br>RAINFALL IN<br>INCHES | 24-HOUR* EFFEC-<br>TIVE RAINFALL<br>IN INCHES | MAXIMUM<br>INFLOW<br>IN C.F.S. | MAXIMUM**<br>OUTFLOW<br>IN C.F.S. | SURCHARGE<br>STORAGE<br>IN FEET | SURCHARGE<br>STORAGE<br>ELEVATION |
|--------------------------|--|---|--------------------------------|-----------------------------------|---------------------------------|-----------------------------------|
| 10                       | 5.0                                    | 2.6   | 560                            | 56                                | 0.80                            | 498.80                            |
| 50                       | 6.5                                    | 4.1   | 860                            | 110                               | 1.26                            | 499.26                            |
| 100                      | 7.0                                    | 4.6   | 960                            | 132                               | 1.42                            | 499.42                            |
| 1/2 MPF<br>=             | 11.9                                   | 9.5   | 3120                           | 1418                              | 4.93                            | 502.93                            |
| TEST FLOOD               |  |   |                                |                                   |                                 |                                   |

\*Infiltration assumed as 0.1"/hour

\*\*Lake assumed initially full at spillway crest elevation 498.0  
(Top of dam = 502.0.)

## NOTES:

1.  $Q_{10}; Q_{50}; Q_{100}$ ; inflow discharges computed by approximate methodology of Soil Conservation Service.
2. 1/2 MPF and "test flood" computation based on COE instructions and guidelines.
3. Maximum capacity of spillway without overtopping the top of the dam elevation 502.0 is equal to 624 C.F.S.
4. All discharges indicated are dependent upon the continued integrity of upstream storage reservoirs.
5. Surcharge storage is allowed to overtop the dam when exceeding the spillway capacity.

b. Experience Data

1. Spillway:

1938 Flood      Q outflow = 270 cfs  
Surcharge = 2.75 feet (estimated)

The Dam was sandbagged to prevent overtopping. Water levels approached within one foot of the dam crest elevation. As a result of this flood the spillway was doubled in size.

1955 Flood      No records available

1968 Flood      Q outflow = 65 cfs (estimated)  
Surcharge = 0.75 feet

2. Outlet and Intake Structure: A vertical pier which extends approximately 60 feet out into the lake is oriented normal to and flush with the top of the embankment and contains the control mechanism for the outlet. This consists of an old manual hoist, which, through a series of gears, lifts vertically an 8.0 inch wooden gate post. The only information available for the assembly in which the gate seats is a sketch made by a diver in May, 1968. This sketch indicates that the gate rides in a tapered

slot on the face of the pier. The gate seats in front of the outlet conduit. A timber trash rack in front of the gate was in bad disrepair according to the diver survey. (See attached sketches - Appendix B). Seating of this gate has become a serious problem.

c. Visual Observations:

1. Spillway bed is undermined and in poor condition.
2. Spillway training walls are eroded, dislodged and collapsed on the downstream slope.
3. Intake control structure is in urgent need of repairs.
4. Emergency spillway was refilled and no longer exists, but filling was incomplete or settlement of the placed material has occurred, leaving a low spot in the crest of the dam.

d. Overtopping Potential: Spillway is hydraulically inadequate and structurally unsafe to pass the Spillway Design Flood. The surcharge created by this Flood will overtop the lowest point on the dam crest by approximately 0.90+ feet. The 100-

year storm event with hurricane-type winds will produce wave set-up and ride-up that would be dangerous to the dam because of inadequate free-board. The upstream face of the dam requires additional slope protection for wave action. The maximum discharge capacity of the spillway without overtopping the dam is 624 cfs which is 44% of the test flood outflow discharge of 1418 c.f.s. See Appendix D for Spillway Rating Curve.

## SECTION 6

### STRUCTURAL STABILITY

#### 6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observations: There were several signs of structural distress evident during the visual inspection that are discussed in various sections of this report (seepage, spillway slab, spillway, training walls, outlet works pier, etc.)
- b. Design and Construction Data: No such data are available and an evaluation cannot be made.
- c. Operating Records: The gatekeeper has indicated that 12-inch size stones with mortar on them passed out of the 18-inch cast iron discharge conduit. No evidence of such major damage was visible at the time of the inspection. The

surface erosion holes mentioned in Section 3.1

(c) may be related to such losses.

- d. Post-Construction Changes: Available correspondence indicates that sandbags were placed on the crest during the 1938 hurricane, but that those sandbags were not found to be needed. After the hurricane, the spillway was widened from 13.0 feet to its present 26.0 feet and a concrete cutoff 3 to 4 feet deep was apparently placed beneath the spillway channel at an unrecorded location.

An emergency spillway was cut into the right side of the dam. The bottom of the channel, which was unlined, was 2.0 feet above the present spillway channel, according to the correspondence. This emergency spillway was subsequently filled with earth of an unspecified type in an unspecified manner by Town of Columbia work crews.

Trees up to 20 inches in diameter were allowed to grow in substantial numbers on the upstream and downstream sides of the dam. Subsequently, these trees were cut, leaving stumps and roots that are now rotting. The brush was most recently cleared from the downstream face of the dam in the fall of 1977, so that at the time of the inspection,



there was no brush present, only grass and low growth up to about 18 inches in height.

The downstream face of the dam was, according to the correspondence, flattened to its present slope by adding fill. The fill type was not specified, nor was the method of placement. The fill was added in a wedge from the crest to the top of the toe wall in an apparent effort to make the dam more stable. Placement of such additional weight above the toe wall reduces the stability of the downstream slope. If this fill is less pervious than the embankment itself, then the stability of the downstream slope would be reduced. Only if the fill were equally or more pervious than the embankment, and if it extends down beyond the toe wall, would the downstream slope stability be improved.

- e. Seismic Stability: This dam is in seismic Zone 1 and, hence, does not have to be evaluated for seismic stability according to the Recommended Guidelines.

## SECTION 7

### ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

#### 7.1 DAM ASSESSMENT

- a. Condition: Based on the visual inspection, records available of the site and past operational performance, the dam is judged to be in poor condition. A review of the limited data available reveals that there are areas of concern which must be corrected in order to assure the long term performance of the dam.

These concerns are as follows:

1. The spillway bed is undermined over a substantial area, has steep, unprotected downstream slopes with loose rubble masonry which is generally dislodged, settled or eroded. Prior patching with dumped concrete has been ineffective. High impoundment levels cause flow beneath the spillway floor slab. These flows could produce serious undermining and erosion and could lead to subsequent failure of the dam.
2. Surface erosion holes adjacent to the operating mechanism at the upstream end

of the gate support structure may be due to erosion through holes in the masonry or into the discharge conduit. Observable evidence at the site does not indicate which way the material is being lost.

Loss of material through the outlet would be dangerous to the integrity of the dam.

3. It was reported that closing the gate of the outlet works has become increasingly difficult with leakage and possible clogging occurring. In April of this year it was reported that, to prevent this leakage, cinders were dumped immediately upstream of the gate face. Unless immediate repair to the gate is undertaken, water levels cannot be controlled.
4. Large trees were allowed to grow on both embankment faces and were subsequently cut. Roots of these trees located on both the upstream and downstream dam slopes continuously rot and form increasingly dangerous discontinuities in the embankment where seepage and erosion

may concentrate. These stumps should be given special attention during future inspections to watch for any signs of developing seepage, until a program for their subsequent removal has been developed. It is particularly important that embankment slopes be well maintained in order that inspectors can closely discern changes that may occur.

5. Significant seepage was observed exiting from several locations along the downstream toe of the dam and from the abutments. Seepage was observed and reported to flow under the spillway floor slab and to exit on the downstream slope of that channel. The zone outside of the 18 inch diameter discharge conduit on the downstream end was wet. Although these seepage conditions may have been occurring for many years, continued seepage aggravated by a rise in the water level behind this dam may, over a period of time, lead to internal erosion (piping) of the dam.

6. The spillway capacity does not satisfy the screening criteria established by the Corps of Engineers for the Spillway Design Flood. The adopted storm event (1/2 Probable Maximum Flood) overtops this dam. The freeboard allowance is also inadequate for the 100-year recurrence interval storm event (see Appendix D).
  7. Both east and west spillway training walls on the downstream slope show significant signs of wear with stones dislodged, or collapsed into the spillway bed.
  8. There is no proper and regular maintenance and inspection program for the dam, nor is there a formal warning system for emergency situations.
- B. Adequacy of Information: The information available is such that the assessment of the condition of this dam must be based primarily on the visual inspection and the past operational performance of the structure.
- C. Urgency: It is considered that the recommendations suggested below be implemented

within 180 days of receipt of this Phase 1 report.

- D. Need for Additional Information: There is no evidence that formal engineering analyses were ever performed for this dam. The visual inspection and operational history indicate that attention should be given to the collection of current data in order that the recommendations listed below may be implemented.

## 7.2 RECOMMENDATIONS

- a. Facilities: In view of the concerns for the condition of Columbia Lake Dam, and the lack of engineering backup data, it is recommended that the following measures be undertaken by the Owner.
1. Engage the services of an engineer experienced in the design of earthen dams to collect, analyze and develop designs to accomplish these recommendations.
  2. Institute immediately an analysis for the short term repair and/or rehabilitation of the present outlet works gate in order that control of the water level can be maintained.

3. Initiate an examination and design to develop and implement short term repairs to the spillway to prevent further undermining and potential erosion.
4. Examine the present seepage emanating from the downstream toe and design a system for collection and monitoring this flow in order that changes in flow quantity and sediment transport can be detected.
5. Investigate the cause and correct the surface erosion holes on the gate mechanism pier.
6. Redesign and reconstruct the dam to provide adequate spillway capacity, surcharge storage capability, freeboard, slope protection and outlet works capacity using current hydrolic criteria.
7. Implement immediately a limited subsurface boring and testing program to accomplish the above items.

### 7.3 REMEDIAL MEASURES

- a. Alternatives: As an alternate to the immediate commencement of studies to upgrade the structure Columbia Lake water surface levels should

be lowered and maintained at a level well below the spillway crest. That reduced level should be controlled to provide storage for storm events.

b. Operations and Maintenance Procedures: While the dam has had some maintenance, it is considered important that the following items be attended to as early as is practical:

1. Develop and commence a regular inspection and maintenance schedule for the facility.
2. Incorporate in the above program monitoring of the seepage and examination of the tree stumps on the slopes. Once a procedure has been developed for the removal of the rotting stumps and roots, incorporate this procedure into the regular maintenance program.
3. Develop a system for the recording of data with regard to items such as: water levels, discharges, time and drawdown to assist those responsible for the monitoring of the structure.
4. Prepare an "Emergency Action Plan" to prevent or minimize the impact of failure,



listing the expedient action to be taken  
and authorities to be contacted.

5. Because of the concerns for this dam and  
the limited data available, an around-the-  
clock surveillance should be instituted  
during periods of high precipitation.

APPENDIX A  
VISUAL INSPECTION CHECK LIST

VISUAL INSPECTION CHECK LIST  
PARTY ORGANIZATION

PROJECT COLUMBIA LAKE DAM

DATE 18 MAY 1978

TIME 0830 - 1630

WEATHER CLOUDY - RAIN

W.S.ELEV. \_\_\_\_\_ U.S. \_\_\_\_\_ D.S.

PARTY :

|                        |                       |                      |            |
|------------------------|-----------------------|----------------------|------------|
| 1. <u>R.W. LONG</u>    | <u>CEM</u>            | 6. <u>SAT KHANNA</u> | <u>CEM</u> |
| 2. <u>E.A. REED</u>    | <u>CEM</u>            | 7. _____             | _____      |
| 3. <u>S. POULOS</u>    | <u>GEI</u>            | 8. _____             | _____      |
| 4. <u>R. BROWN</u>     | <u>CEM</u>            | 9. _____             | _____      |
| 5. <u>V. GALGOWSKI</u> | <u>STATE OF CONN.</u> | 10. _____            | _____      |

PROJECT FEATURE

INSPECTED BY

REMARKS

|           |       |       |
|-----------|-------|-------|
| 1. _____  | _____ | _____ |
| 2. _____  | _____ | _____ |
| 3. _____  | _____ | _____ |
| 4. _____  | _____ | _____ |
| 5. _____  | _____ | _____ |
| 6. _____  | _____ | _____ |
| 7. _____  | _____ | _____ |
| 8. _____  | _____ | _____ |
| 9. _____  | _____ | _____ |
| 10. _____ | _____ | _____ |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DAM DATE 18 MAY 1978  
 INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_  
 INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED  | CONDITION   |
|---|---|
| <u>DAM EMBANKMENT</u>                                 |   |
| Crest Elevation                                       | Elevation 502.0   |
| Current Pool Elevation                                | Elevation 498.0   |
| Maximum Impoundment to Date                           | See Section 1   |
| Surface Cracks  | None observed   |
| Pavement Condition                                    | No pavement, grass covered  |
| Movement or Settlement of Crest                       | Depression about 6' to right of spillway wall on top of crest. About 3" below up and downstream crest line.   |
| Lateral Movement                                      | None observed   |
| Vertical Alignment                                    | Surface is too irregular to judge alignment. No pronounced misalignment observable.   |
| Horizontal Alignment                                  |   |
| Condition at Abutment and at Structures               | At right abutment dumped fill used to seal emergency spillway. Slight depression in this zone. Fill could be loose. Left abutment is spillway wall. |
| Indications of Movement of Structural Items on Slopes | None observed.  |
| Trespassing on Slopes                                 | Free Access. Crest grass is worn thin.  |
| Sloughing or Erosion of Slopes or Abutments           | Downstream slope very slightly gullied by surface erosion. One animal hole downstream just above toe wall.  |
| Rock Slope Protection - Reprap Failures               | Riprap sloughing to left of upstream jetty. Slope is eroded from wave action.   |
| Unusual Movement or Cracking at or near Toes          | None Observed   |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DAM DATE 18 May 1978

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED                           | CONDITION  |
|--|--|
| DAM EMBANKMENT                           |  |
| Unusual Embankment or Downstream Seepage | Several seeps downstream on left and right sides. All appear to be silt free |
| Piping or Boils                          | None observed  |
| Foundation Drainage Features             | None   |
| Toe Drains                               | None   |
| Vegetation                               | Several old stumps on both faces. Rotting.                                   |
| Instrumentation System A-2               | None   |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DAM DATE 18 MAY 1978  
 INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_  
 INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED   | CONDITION   |
|--|---|
| <u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u> |   |
| a. Approach Channel  | Riprap apron  |
| General Condition  | Poor to fair  |
| Loose Rock Overhanging Channel                                       | None observed   |
| Trees Overhanging Channel  | None observed   |
| Floor of Approach Channel  | Natural w/riprap apron grouted  |
| b. Weir and Training Walls   |   |
| General Concition of Concrete  | Dry rubble walls westerly side good except for downstream end.<br>Grouted rubble wall easterly side good except for downstream end.<br>Slab - Grouted stone, poor condition undermined.<br>Downstream end bad |
| Rust or Staining   | None observed   |
| Spalling   | N/A   |
| Any Visible Reinforcing  | None observed   |
| Any Seepage or Efflorescence   | None observed   |
| Drain Holes  | N/A   |
| c. Discharge Channel   |   |
| General Condition  | Poor  |
| Loose Rock Overhanging Channel                                       | Yes - Retaining wall (not natural rock cut).  |
| Trees Overhanging Channel  | Recently cleared + overhanging trees.   |
| Floor of Channel   | Natural- Partially obstructed with boulders   |
| Other Obstructions   | Downstream highway culvert  |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DAM DATE 18 MAY 1978

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED                              | CONDITION  |
|---|--|
| <u>OUTLET WORKS - CONTROL PIER</u>          |  |
| a. Concrete and Structural                  |  |
| General Condition                           | Dry rubble construction earth filled<br>' poor to fair.  |
| Condition of Joints                         | Open joints ungrouted  |
| Spalling                                    | N/A  |
| Visible Reinforcing                         | N/A  |
| Rusting or Staining or Concrete             | None observed  |
| Any Seepage or Efflorescence                | Sinkholes around gate control<br>Mechanism   |
| Joint Alignment                             | N/A  |
| Unusual Seepage or Leaks in Gate<br>Chamber | Considerable leakage noticed on<br>downstream face in area of outlet pipe<br>could be unseated gate, or cracks in<br>pipe, etc.  |
| Cracks                                      | None observed  |
| Rusting or Corrosion of Steel               | Rusting observed in discharge water<br>or downstream face.   |
| b. Mechanical                               |  |
| Air Vents                                   | Manually operated gate. Locked.<br>Exposed to weather. Rusted.<br>Last operated in April, 1978 and<br>problems in seating occurred. Finally<br>sealed by dumping cinders. Gates and<br>trash rack are wooden and reportedly in<br>need of repair or replacement. |
| Float Wells                                 |  |
| Crane Hoist                                 |  |
| Elevator                                    |  |
| Hydraulic System                            |  |
| Service Gates                               |  |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DAM DATE 18 MAY 1978

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED                           | CONDITION |
|--|-----------|
| OUTLET WORKS - CONTROL PIER (cont.)      |           |
| Emergency Gates                          | None      |
| Lightning Protection system              | None      |
| Emergency Power System                   | None      |
| Wiring and Lighting System in gatehouse. | None      |



# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DATE 18 MAY 1978  
 INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_  
 INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED  | CONDITION  |
|---|--|
| <u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u> |  |
| a. Approach Channel                                       |  |
| Slope Conditions  | Not observed. Below water.   |
| Bottom Conditions   | Not observed. Below water.   |
| Rock Slides or Falls                                      | Not observed. Below water.   |
| Log Boom  | None.  |
| Debris  | Not observed. Below water.   |
| Condition of Concrete Lining                              | Not observed. Below water.   |
| Drains or Weep Holes                                      | Not observed. Below water.   |
| b. Intake Structure                                       |  |
|   | Stone faced, earth filled pier on upstream face jutting out into Columbia Lake. Trash rack, and gate mechanism located in southerly tip of pier. Inspected as part of dam. |
| Condition of Concrete                                     | Not observed. Underwater.  |
| Stop Logs and Slots                                       | In wet well of chamber. Not observed.  |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DATE 18 MAY 1978

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED  | CONDITION   |
|---|---|
| <p><u>OUTLET WORKS - CONDUIT</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining on Concrete</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Cracking</p> <p>Alignment of Monoliths</p> <p>Alignment of Joints</p> <p>Numbering of Monoliths</p> | <p>Conduit - 18" diameter cast iron pipe at downstream end. Appears to be rusted and mishapen at the outlet on the downstream face.</p> |

# PERIODIC INSPECTION CHECK LIST

PROJECT COLUMBIA LAKE DATE 18 MAY 1978

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

INSPECTOR \_\_\_\_\_ DISCIPLINE \_\_\_\_\_

| AREA EVALUATED  | CONDITION                                    |
|---|--|
| <u>OUTLET WORKS - OUTLET STRUCTURE AND<br/>OUTLET CHANNEL</u> |  |
| General Condition of stone masonry                            | Dry stone box culvert 16" x 40"              |
| Rust or Staining  | Considerable rust staining from outlet       |
| Spalling  |  |
| Erosion or Cavitation   |  |
| Visible Reinforcing   | Dry rubble construction enclosing<br>a pipe. |
| Any Seepage or Efflorescence                                  | Considerable seepage noted.                  |
| Condition at Joints   |  |
| Drain holes   |  |
| Channel   | Natural earth channel                        |
| Loose Rock or Trees Overhanging<br>Channel                    | Yes  |
| Condition of Discharge Channel                                | Poor to fair                                 |

## APPENDIX B

### I. Records for dam can be found at:

1. Town Hall, Box 165, Columbia, CT 06237

2. Department of Environmental Protection

State of Connecticut

State Office Building

Hartford, Connecticut 06115

Attention: Mr. Victor Galgowski,

Dam Safety Engineer

Water and Related Resources Unit

### II. Inspection Correspondence

### III. Sketches, Drawings

**MOZZOCHI ASSOCIATES**

**CIVIL ENGINEERS**

GLASTONBURY, CONN. 06033  
217 HESBON AVENUE  
PHONE 833-9401

PROVIDENCE, R. I. 02903  
100 WETTESSET STREET  
PHONE 421-0420

PARTNERS

September 22, 1971

JOHN LUCHS, JR.  
STUART J. BECKERMAN

REPLY TO: Glastonbury

William H. O'Brien, III  
Civil Engineer  
Water Resource Commission  
State Office Building  
Hartford, Connecticut 06115

STATE WATER RESOURCES  
COMMISSION  
**RECEIVED**

SEP 23 1971

ANSWERED \_\_\_\_\_ Re: Columbia Lake Dam  
REFERRED \_\_\_\_\_ Columbia, Connecticut  
FILED \_\_\_\_\_ Our File #57-73-43

Dear Mr. O'Brien:

Reference is made to our report of April 17th, 1970, for this dam. This letter reported on the hydraulics of the present structure with several recommendations.

I revisited the site on September 7th, 1971 and noted the following:

1. Several large trees were up-rooted by the recent strong winds (August 28th, 1971).
2. The spillway is partially clogged with branches from a tree that was felled and cut up recently on property to the west of the spillway.
3. Growth is beginning to reappear on the embankment. Sassafras, wild cherry and other trees are taking root.
4. The area at the easterly end of the embankment, which once qualified as a crude emergency spillway, has been filled in and is presently higher than the rest of the embankment.
5. Exit channel below level control section deteriorating.

The hydraulics for this structure were checked again and determined to be correct. In light of your letter to check the stability of the emergency spillway and my recent visit, the following recommendations are


made:

1. Raise embankment 1.7 feet to provide 3' freeboard and add riprap protection.
2. Exit channel below control level section should be repaired. It is recommended that concrete be used to fill voids between the stones (as has been done on the control section) to hold in position. Velocity varies from 9 to 15 feet per second dictating additional protection.
3. Remove fallen trees and brush from the downstream area.
4. Initiate a maintenance program for the structure.

Very truly yours,

MOZZOCHI ASSOCIATES

By

  
John Luchs, Jr., Senior Partner

JLW:red  
file

**MOZZOCHI ASSOCIATES**

**CIVIL ENGINEERS**

**PARTNERS**

JOHN LUCHS, JR.  
STUART J. BECKERMAN

April 17, 1970

GLASTONBURY, CONN. 06033  
217 HEDDEN AVENUE  
PHONE 633-6401

PROVIDENCE, R. I. 02903  
189 WETMORE STREET  
PHONE 421-0420

Reply To: Glastonbury

William H. O'Brien III, Civil Engineer  
Water Resources Commission  
State Office Building  
Hartford, Connecticut 06115

Re: Columbia Lake Dam  
Columbia, Connecticut  
Our File #57-73-43

Dear Mr. O'Brien:

The proposed dam was inspected on March 3, 1970 to verify dimensions against a sketch prepared by Mr. John J. Mozzochi in 1963.

It is an existing dam of 251' to 301' length with a 16' top width. The spillway is on the western end of the embankment. The level concrete section is 301' in length and 26' wide. The inlet floor is 24' wide and the downstream section drops off sharply and leads to a 41'-6" box culvert under the roadway crossing the valley downstream of the dam.

The spillway and the spillway are vertical dry wall construction and the dam is a concrete (telford type). The spillway crest is 41'-2" above the top of the dam. There is a draw-down conduit (stone construction downstream) 11'-6" x 2'-0" with a gate in a shaft-type structure protruding into the lake to control the water level. This structure is ignored in our calculations as insignificant.

The following is a total water shed area of three square miles and a water surface elevation of 200 feet above normal water surface elevation. Flood routing studies are to be made to check the capacity of the existing spillway and the available floodboard for the following:

- 1. 50 year flood - 6 hour duration
- 2. 100 year flood - 6 hour duration
- 3. 1.5 ft. high water - 6 hour duration

The design of the spillway and floodboard are tabulated below.

STATE OF CONNECTICUT

RECEIVED

APR 20 1970

100

100

100

April 17, 1970

| <u>TYPE OF STORM</u>                  | <u>RAINFALL (inches)</u> | <u>DIRECT RUN-OFF (inches)</u> | <u>MAX. WATER SURFACE ELEVATION ABOVE SPILLWAY CREST (feet)</u> | <u>FREEBORD (feet)</u> |
|---------------------------------------|--------------------------|--------------------------------|---|------------------------|
| 50 yrs storm<br>6 hrs duration        | 4.5                      | 2.9                            | 1.6   | 2.6                    |
| 100 yrs storm<br>6 hrs duration       | 5.1                      | 3.5                            | 1.9   | 2.3                    |
| 1.5 x 100 yrs storm<br>6 hrs duration | 7.6                      | 5.8                            | 2.9   | 1.3                    |

With a fetch of 1 mile of open water, a minimum of 3' of ripraped freeboard is prudent and some corrective measures are required to attain this. Referring to Mozzochi's letter dated April 25, 1963, the following recommendations are in substantial agreement.

1. Provide additional spillway on the easterly end of dam or raise top of dam..
2. Clean debris from area between dam embankment and road embankment to prevent clogging of the 4'x6' box culvert under the road.

Very truly yours,

MOZZOCHI ASSOCIATES

By John Lucns, Jr.  
John Lucns, Jr. - PartnerJLjw/ed  
File



## INTERDEPARTMENT MAIL

DATE DECEMBER 7, 1967

|         |                             |            |     |
|---------|-----------------------------|------------|-----|
| TO      | FILE                        | DEPARTMENT | WRC |
| FROM    | WILLIAM H. O'BRIEN          | DEPARTMENT | WRC |
| SUBJECT | COLUMBIA LAKE DAM, COLUMBIA |            |     |

On December 6, 1967, the undersigned visited the above dam and made the following observations:

1. The water level had been lowered several feet below normal, I assume to allow property owners to make repairs to docks, etc.
2. It appeared that some work had been done in constructing an emergency spillway on the east end of the dike. In any event, there was a low area at the extreme easterly section of the dam which was approximately 25 feet in width and at an elevation approximately 2 feet above normal pond level. However, there was a pile of dirt in the middle of this "spillway" and there was no protection of the side slopes of this spillway. The intent of suggesting an emergency spillway in this area was apparently to take advantage of a low area formed by the access road to the dam from Route #87. In fact, with suitable erosion protection, part of this roadway could be used as part of the emergency spillway channel. In any event, the emergency spillway was in no way complete, but it appeared that it could be with a minimum of effort.
3. There was a 12 inch tree growing very close to the outlet end of the drawdown structure which should be cut down.
4. There was a great deal of debris in the lower principal spillway channel such as fallen rocks, and small trees and some brush. This should be cleaned up.
5. Apparently no work in flattening the down-stream slope had been done.

*William H. O'Brien*  
 WILLIAM H. O'BRIEN  
 CIVIL ENGINEER

JOHN J. MOZZOCHI AND ASSOCIATES  
CIVIL ENGINEERS

GLASTONBURY, CONN.  
317 HERRON AVENUE  
PHONE 633-8401

PROVIDENCE 3, R. I.  
188 OYER STREET  
PHONE GASPER 1-0420

JOHN J. MOZZOCHI

March 11, 1966

ASSOCIATES

OWEN J. WHITE  
JOHN LUCKE, JR.  
ECTOR L. GIOVANNINI

REPLY TO: Glastonbury

William H. O'Brien, III  
Water Resources Commission  
State Office Building  
Hartford, Connecticut 06115


Re: Our File 57-73-43  
Columbia Lake Dam

Dear Mr. O'Brien:

In accordance with your instructions of March 7th, I re-inspected the referenced dam on March 8th and found that Items No. 1, Remove all trees from the embankment, and Item No. 2, Remove all debris from spillway, (as called for in my report of April 25, 1963) have been accomplished satisfactorily. The other items calling for an emergency spillway and flattening of the downstream slope have not been accomplished.

I suggest that this matter be called to the Town's attention, as soon as possible.

Very truly yours,

  
John J. Mozzochi and Associates  
Civil Engineers

JTM:hk

|                                     |       |
|-------------------------------------|-------|
| STATE WATER RESOURCES<br>COMMISSION |       |
| RECEIVED                            |       |
| MAR 14 1966                         |       |
| ANSWERED                            | _____ |
| REFERRED                            | _____ |
| FILED                               | _____ |

**JOHN J. MOZZOCHI AND ASSOCIATES**  
CIVIL ENGINEERS

JOHN J. MOZZOCHI  
ASSOCIATES  
OWEN J. WHITE  
JOHN LUCHE, JR.  
ECTOR L. GIOVANNINI

April 25, 1963

FILED  
APR 26 1963  
RECEIVED  
FILED

GLASTONBURY, CONN.  
217 WEBER AVENUE  
PHONE 633-0401

PROVIDENCE 3, R. I.  
200 DYER STREET  
PHONE GASPER 1-0420

REPLY TO: Glastonbury

William S. Wise-Director  
Water Resources Commission  
State Office Building  
Hartford 15, Connecticut

Re: Our File 57-73-43  
Columbia Lake Dam  
Columbia, Connecticut

Dear Mr. Wise:

As per instructions received from Robert McCabe, I contacted Mr. Clair Robinson, First Selectman of Columbia, and made an inspection of the referenced dam on April 24th. This is a town-owned structure.

Mr. Robinson has been selectman in Columbia for 42 years and is very well acquainted with the recent history of the dam. He informs me that in 1938, the dam was sand-bagged to prevent it from being overtopped and that a wash-out occurred at the easterly end of the embankment. This washout was refilled but apparently to an elevation that is now higher than the dam.

This is an earthen dam about 260' long with a maximum height of about 25 - 30 feet. It has a spillway about 26' wide and 40' long with a freeboard of 4 feet. The lake has an area of about 270 acres and a clear reach of about a mile south of the dam. The town has riprapped the lake side of the dam against wave action. There is an excellent sod cover on top of the dam but there are also numerous large diameter trees growing thereon. The downstream slope of the dam appears to be steeper than a 2 to 1 slope. A drawdown gate is in good operating condition and is opened each Fall to lower the pond level through the winter. However, the discharge opening downstream is only 1-1/2' x 2' and therefore adds only slightly to the capacity of the spillway.

With a minimum freeboard of 1 foot, I calculated the discharge capacity of the spillway at 360 C.F.S. For a total drainage area of 3.1 sq. miles, I believe this spillway has insufficient capacity as already indicated by the experience in 1938.

I recommend the following actions be required:


1. Remove all trees from the embankment;
2. Remove all debris from the spillway;
3. Excavate an emergency spillway at the east end of the dike in natural ground, even though it may be ledge, at an elevation of about 1-1/2 feet above the main spillway and at a minimum width of 25 feet;

4. Flatten the downstream slope of the dam to a slope of 3 horizontal to 1 vertical.

The only alternate to (3) above would be to raise the dam at least 3 feet to provide additional freeboard. I believe the emergency spillway would be more economical and safer.

In accordance with our phone discussion, I am transmitting a copy of this letter to Mr. Robinson to expedite his report to a Town Meeting on Saturday, April 27th.

Very truly yours,

  
John J. Mozzochi and Associates  
Civil Engineers

JJM:hk

NOV 7 1933  
STATE WATER COMMISSION

#114 Thayer Building  
Norwich, Connecticut

November 6, 1933

Mr. C. L. Robinson  
First Selectman  
Columbia, Connecticut

Dear Mr. Robinson:

After visiting Columbia Lake with you and Mr. Hutchins I find from the topographical map that the drainage area contributing to the Lake is about four square miles but the hills are not particularly steep and you have a large pond. You described to me the situation in the storm of September 1928 in which you had quite high waves on the Lake which washed the embankment somewhat so that you felt obliged to place sand bags along the upstream edge. There was no danger of the embankment being overtopped but whatever damage was done was caused by the wave action. The protection of the embankment slope by rip rap placed during the past year was well done and should protect the embankment from further erosion by the waves.

In regard to widening the spillway it is my recommendation that this be done as the width of the present spillway of 13 feet and with the abutment walls about 6 feet higher it does not come to our requirements. There was some indication on the ground that the spillway had been narrowed up, although I very much doubt this being done for it is hard to conceive why it should be. My recommendation is that you double up the width of the spillway carrying the stone abutments in a straight line, as you suggest, until it meets the steep slope of the existing channel. The new spillway, unless it comes on ledge, which seems improbable, should be paved as you suggest with stone pavers about 12" deep. I would also recommend, unless the material is extremely hard on the new section of the spillway, that you put in a 12" concrete outer wall on the new section of the spillway having this wall go down 3' or 4' into hard material.

I think the above work is nothing but what can be done by your own Town forces under your supervision.



With kind regards to both you and Mr. Hutchins and remembering with pleasure how we three settled the affairs of the state, I remain

Very truly yours,

*J. B. Palmer*


Member, State Board of Supervision


132/3



ELEVATION OF DOWNSTREAM FACE OF DAM  
SCALE: HORIZ. 1"=40'  
VERT. 1"=10'


COLUMBIA LAKE DAM







1



2

Timber Gate

Gate Operating Device

18" Cast Iron

Edge of Water

100

95

96

97

End of Concrete

90

85

80


80

75

75

75


62



3

RECEIVED  
OFFICE OF THE  
DIRECTOR

RECEIVED  
OFFICE OF THE  
DIRECTOR



Gravel Access Road


Gate

Edge of pavement

TRUMBULL

HIGH

4



TOWN OF  
COLUMBIA, CONNECTICUT

COLUMBIA LAKE DAM

Scale: 1" = 80'

Date: Assumed

Prepared by: E. A. [illegible]

July 1964  
[illegible]  
[illegible]

APPENDIX C  
SELECTED PHOTOS

C-6

APPROXIMATE ROCK JOINT  
ALIGNMENT OBSERVABLE

Edge of Water


C-11

C-3

C-9

C-8

C-7





2

Timber Gate

Gate Operating Device

18" Cast Iron

Edge of Water

C-11

100

95

96

97

100

End of Concrete

90

85

85



90

75

75

C-12

3



LEGEND

95



Gravel Access Road

GOLF


Edge of p

97

TRUMBULL

95

4



# LEGEND



DENOTES SEEPAGE ZONES



SURFACE EROSION HOLES



AREA OF DISLODGED MASONRY AND  
OBSTRUCTED SPILLWAY BED.

## PHOTOGRAPH INDEX

TOWN OF  
COLUMBIA, CONNECTICUT

COLUMBIA LAKE DAM

Scale: 1" = 20'

June 1908

Datum: Assumed

Prepared by: T. A. Brindamour

Manchester, Conn.



C-2 LOOKING EAST AT DOWNSTREAM SLOPE DAM EMBANKMENT



C-3 LOOKING WEST ALONG CREST OF DAM EMBANKMENT




C-4 DOWNSTREAM SLOPE OF SPILLWAY



C-5 SEEPAGE EMANATING  
FROM DOWNSTREAM  
TOE OF SPILLWAY



C-6 CONTROL GATE MECHANISM ON UPSTREAM PIER



C-7 STONE BOX CULVERT  
OUTLET AT EMBANK-  
MENT TOE

NOTE: RUST STAINING






C-8 LOOKING DOWNSTREAM AT ROUTE 87 CULVERT



C-9 STUMP AT TOE WALL ON DOWNSTREAM FACE OF EMBANKMENT




C - 10 SEEPAGE AREA AT DOWNSTREAM  
TOE



C-II SINKHOLES AT GATE MECHANISM

APPENDIX D  
HYDROLOGIC COMPUTATIONS



A. Size Classification

Height of Dam = 27.0 feet; Hence SMALL

at crest elevation reservoir storage = 3370 AC-ft., hence INTERMEDIATE

adopted size category INTERMEDIATE

B. Hazard Potential

DAM IS LOCATED IN AN AREA THAT IS NOW PREDOMINANTLY RURAL.  
FAILURE OF THE DAM IN THE NEAR FUTURE MAY NOT CAUSE DAMAGE TO  
LIFE OR HOMES BUT WILL INVOLVE APPRECIABLE ECONOMIC LOSS OF  
RECREATIONAL FACILITIES. THE FAILURE HAS A DISTINCT POTENTIAL OF  
WASHING OUT ROUTE 87 AND THE UTILITIES ADJACENT TO IT.

It is estimated from the rule of "thumb" failure hydrograph as follows:

| <u>Category</u>    | <u>Loss of Life</u> | <u>Economic Loss</u>           |
|--------------------|---------------------|--------------------------------|
|                    |                     | Homes =                        |
|                    |                     | Buildings = } <u>NIL</u>       |
|                    |                     | Farms = }                      |
|                    |                     | Miscellaneous = <u>YES</u>     |
| <u>SIGNIFICANT</u> | <u>NONE</u>         | Highways or roads = <u>YES</u> |

C. Hazard                      Size                      "Test Flood" or Spillway Design Flood

SIGNIFICANT                      INTERMEDIATE                      1/2 PMF TO PMF

Adopted  
 S.D.F. (test flood) = 1/2 PMF = 1000 CSM

Adopted value of test flood due to watershed characteristics = 1000 CSM

Estimating Maximum Probable Discharges - Inflow and Outflow Values Date of Inspection: 5/18/78

Name of Dam COLUMBIA LAKE DAM ; Location of Dam COLUMBIA LAKE BROOK Town HOP RIVER, CT.

Watershed Characterization ROLLING WITH FLAT SLOPES

Adopted "test" flood = HALF PMF = 1000 CSM = 3120 C.F.S.

D.A. = Drainage Area = 3.12 Square Miles = Acres

S.A. = Surface Area of Reservoir = 0.422 Square Miles = 270 Acres

Shape and Type of Spillway = BROAD CRESTED, UNCONTROLLED, OVERFLOW

B = Width of Spillway = 26.0 feet; C = Coefficient of Discharge = (3.10 - Friction) = 3.00

Maximum Capacity of Spillway Without Overstopping = 624 C.F.S. = 20 % of test flood

Top of Dam Elevation = 502.00 ; Spillway Crest Elevation = 498.00

Length of Dam = 295 feet

| Name of Dam   | Test Flood      |      | Inflow Characteristics | Outflow Characteristics First Approximation |                        |                     | Outflow Characteristics Second Approximation |                        |                        | Outflow Characteristics Third Approximation |                     |                        |                       |
|---------------|-----------------|------|------------------------|---|------------------------|---------------------|--|------------------------|------------------------|---|---------------------|------------------------|-----------------------|
|               | Q <sub>P1</sub> | CFS  |                        | h <sub>1</sub> in feet                      | S <sub>1</sub> in inc. | Q <sub>P2</sub> CFS | h <sub>2</sub> in feet                       | S <sub>2</sub> in inc. | S <sub>3</sub> in inc. | h <sub>3</sub> in ft.                       | Q <sub>P3</sub> CFS | S <sub>4</sub> in inc. | h <sub>4</sub> in ft. |
| 1             | 2               | 3    | 4                      | 5   | 6                      | 7                   | 8  | 9                      | 10                     | 11  | 12                  | 13                     | 14                    |
| COLUMBIA LAKE | 1000            | 3120 | 6.00                   | 9.74  | 2851                   | 5.85                | 9.50   | 6.49                   | 4.0                    | 624   | 7.99<br>= 8.00      | 4.93                   | 1418                  |

Q<sub>P</sub> = Discharge; h = surge height S = Storage in inches

"Rule of Thumb Guidance for Estimating  
Downstream Dam Failure Hydrograph"

BASIC DATA

Name of dam COLUMBIA LAKE DAM Name of town HOP RIVER - Conn  
 Drainage area = 3.12 sq.mi. Top of dam 502.0  
 Spillway type = UNCONTROLLED OVERFLOW Crest of spillway 498.0 NGVD  
 Surface area at crest elevation = 270 Acres  
 Reservoir bottom near dam = 471.0 NGVD  
 Assumed side slopes of embankments = 2:1  
 Depth of reservoir at dam site 27 ft =  $y_0$  = 27.0 ft.  
 Mid-height elevation of dam = 484.50 NGVD  
 Length of dam at crest = 260 feet  
 Length of dam at mid-height = 206 feet  
 40% of dam length at mid-height =  $W_b$  = 82 feet ft.  
 Stream height of dam = 28 feet  
 Hydraulic height of dam = 27 feet

Step 1:

| Elevation<br>M.S.L. | RESERVOIR<br>Estimated Storage<br>In AC-ft. = $S$ | Remarks |
|---------------------|---|---------|
| 498.00 - - -        | 3370  |         |
| 499.00 - - -        | 3640  |         |
| 500.00 - - -        | 3910  |         |
| 501.00 - - -        | 4180  |         |
| 502.00 - - -        | 4450  |         |
| 503.00 - - -        | 4720  |         |

Step 2:

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} y_0^{3/2}$$

$$= \underline{1.68} W_b y_0^{3/2} = 19327 \text{ C.F.S}$$



Step 3:

| Reach            | Length<br>in Feet | Stage | Discharge | Remarks |
|------------------|-------------------|-------|-----------|---------|
| L <sub>1-2</sub> | 800               | 470   | 17980     |         |
| "                | "                 | 460   | 4770      |         |
| L <sub>2-3</sub> | 237.5             | 359   | 18608     |         |
| "                | "                 | 358   | 11158     |         |
| L <sub>3-4</sub> | 3000              | 288   | 17826     |         |
| "                | "                 | 285   | 8592      |         |
|                  |                   |       |           |         |
|                  |                   |       |           |         |
|                  |                   |       |           |         |

Notes:

Step 4:

Reach Length 1-2

A)  $Q_{p1} = 19327$  CFS

Stage =  $471.87$

Area =  $915.70$  sq. ft. =  $0.021$  AC-ft.

Length =  $L_{1-2} = 800$  ft.

$V_1 = 16.81$  cu. ft. =  $16.81$  AC-ft.

$S = 4720$  AC-ft.

$\frac{V_1}{S} = 0.0036$  less than 0.5; O.K.

B)  $Q_{p2} \text{ (Trial)} = Q_{p1} (1 - \frac{V_1}{S}) = 19300$  CFS

C) Stage for  $Q_{p-2} = 471.80$

Area =  $910$  sq. ft.

$L_{1-2} = \text{length} = 800$  ft.

$V_2 = 16.8$  AC-ft.

$S = 4720$  AC-ft.

$\frac{V_2}{S} =$  less than 0.5; O.K.

D)  $\frac{V_1 + V_2}{2} = V_{avg} = 16.81$  AC-ft.

$Q_{p-2} = Q_{p-1} (1 - \frac{V_{avg}}{S})$

$= 19300$  CFS

Stage for  $Q_{p-2} = 471.80$

Bed Elevation =  $450.00$

depth =  $21.80$  ft

Step 5:

Reach Length 2-3

$Q_{p2} = 19300$  CFS

Stage =  $471.8$

Area =  $1280$  sq. ft. =  $0.0294$  AC-ft.

Length =  $L_{2-3} = 2375$  ft.

$V_2 = 69.80$  cu. ft. =  $69.80$  AC-ft.

$S = 4720$  AC-ft.

$\frac{V_2}{S} = 0.0147$  less than 0.5; O.K.

$Q_{p-3} \text{ (Trial)} = Q_{p-2} (1 - \frac{V_2}{S}) = 19000$  CFS

Stage for  $Q_{p-3} = 358.90 \approx 359$

Area =  $1280$  sq. ft.

$L_{2-3} = \text{length} = 2375$  ft.

$V_3 = 70$  AC-ft.

$S = 4720$  AC-ft.

$\frac{V_3}{S} = 0.015$  less than 0.5; O.K.

$\frac{V_2 + V_3}{2} = V_{avg} = 70$  AC-ft.

$Q_{p-3} = Q_{p-2} (1 - \frac{V_{avg}}{S})$

$= 19000$  CFS

Stage for  $Q_{p-3} = 359.0$

Bed Elevation =  $355.0$

depth =  $4.0$  ft

AD A144 788

NATIONAL PROGRAM FOR INSPECTION OF NON FEDERAL DAMS  
COLUMBIA LAKE DAM (C1) (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV SEP 78


2/2

UNCLASSIFIED

176 13/13 MI



END  
DATE  
FILMED  
10-84  
DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

Step 4 (con't): Reach Length 3-4

A  $Q_{p-3} = 19000$  CFS

Stage = 288.4

Area = 1120 sq. ft. = AC-ft.

Length =  $L_{3-4} = 3000$  ft.

$V_3 = 77.13$  cu. ft. = AC-ft.

$S = 4720$  AC-ft.

$\frac{V_3}{S} = 0.016$  less than 0.5; O.K.

E  $Q_{p-4} \text{ (Trial)} = Q_{p-3} (1 - \frac{V_3}{S}) = 18734$  CFS

( Stage for  $Q_{p-4} = 288.3$

Area = 1120

$L_{3-4} = 3000$  ft.

$V_4 = 77$  AC-ft.

$S = 4720$  AC-ft.

$\frac{V_4}{S} = 0.016$  less than 0.5; O.K.

1)  $\frac{V_3 + V_4}{2} = V_{avg} = 0.016$  AC-ft.

$Q_{p-4} = Q_{p-3} (1 - \frac{V_{avg}}{S})$   
 $= 18700$  CFS

Stage for  $Q_{p-4} = 288.3$

Bed Elevation = 280.0

depth = 8.3'

(May overflow Route 6)

Step 5 (con't): Reach Length 4-5

$Q_{p-4} =$  CFS

Stage =

Area = sq. ft. = AC-ft.

Length =  $L_{4-5} =$  ft.

$V_4 =$  cu. ft. = AC-ft.

$S =$  AC-ft.

$\frac{V_4}{S} =$  less than 0.5; O.K.

$Q_{p-5} \text{ (Trial)} = Q_{p-4} (1 - \frac{V_4}{S}) =$  CFS

Stage for  $Q_{p-5} =$

Area =

$L_{4-5} =$  ft.

$V_5 =$  AC-ft.

$S =$  AC-ft.

$\frac{V_5}{S} =$  less than 0.5; O.K.

$\frac{V_4 + V_5}{2} = V_{avg} =$  AC-ft.

$Q_{p-5} = Q_{p-4} (1 - \frac{V_{avg}}{S})$   
 $=$  CFS

Stage for  $Q_{p-5} =$

Step 3:

| Reach No. | Distance in Feet | Mean Slope | Adopted "n" | Stage = 4.70 |              |       | Stage = 4.60 |       |     | Stage =      |      |       |       |   |
|-----------|------------------|------------|-------------|--------------|--------------|-------|--------------|-------|-----|--------------|------|-------|-------|---|
|           |                  |            |             | A            | P            | R     | V            | Q     | A   |              | P    | R     | V     | Q |
| 1-2       | $L_{1-2} = 800$  | 0.025      | 0.05        | 800          | 76.6         | 10.44 | 22.5         | 17980 | 300 | 48.28        | 6.21 | 15.90 | 4770  |   |
|           |                  |            |             |              | Stage = 3.59 |       |              |       |     | Stage = 3.58 |      |       |       |   |
| 2-3       | $L_{2-3} = 2375$ | 0.0400     | 0.05        | 1280         | 341          | 3.753 | 14.53        | 18608 | 945 | 330          | 2.86 | 11.89 | 11158 |   |
|           |                  |            |             |              | Stage = 2.88 |       |              |       |     | Stage = 2.85 |      |       |       |   |
| 3-4       | $L_{3-4} = 3000$ | 0.025      | 0.05        | 1120         | 180          | 6.22  | 15.91        | 17826 | 625 | 150          | 5.0  | 13.74 | 8592  |   |
| 4-5       | $L_{4-5} =$      |            |             |              |              |       |              |       |     |              |      |       |       |   |
| 5-6       | $L_{5-6} =$      |            |             |              |              |       |              |       |     |              |      |       |       |   |

Notes: 1. Reach No 1 is at the Dam

2. "n" value is weighted Manning's roughness coefficient


Storage Elevation Estimation Procedure

| Elevation | Depth<br>in Feet | Area<br>Acres | Storage Capacity<br>AC-ft. |            |
|-----------|------------------|---------------|----------------------------|------------|
|           |                  |               | Increment                  | Cumulation |
| 498.00    | — Varies         | 270.00        | —                          | 3370       |
| 499.00    | —                | "             | 270                        | 3640       |
| 500.00    | —                | "             | 270                        | 3910       |
| 501.00    | —                | "             | 270                        | 4180       |
| 502.00    | —                | "             | 270                        | 4450       |
| 503.00    | —                | "             | 270                        | 4720       |

Notes:

PROJECT COLUMBIA LAKE DAMACC. NO. 3155.202SUBJECT DAM FAILURE PROFILESHEET NO. 0-2 OF     COMP.     CHECK     DATE      19     CONT. NO.     DAM FAILURE PROFILE

FAILURE DISCHARGE = 19327 CFS





Overtopping Potential

Spillway crest elevation = 498.00 M.S.L.

Top of dam elevation = 502.00 M.S.L.

Maximum discharge capacity of  
Spillway without overtopping } = 624 C.F.S.


"Test flood" outflow discharge = 1418 C.F.S.

% of "Test flood" carried by  
Spillway without overtopping } = 44 % 1

"Test flood" outflow discharge  
which flows over the dam = 794 C.F.S.


= 56.0 % of "Test flood" 2

$$1 + 2 = 100\%$$



SPILLWAY RATING CURVE  
COLUMBIA LAKE DAM

PROJECT COLUMBIA LAKE DAM ACC. NO. 3155.202  
SUBJECT DAM FAILURE PROFILE X-SECTIONS SHEET NO. 510 OF 5  
DATE May 1978  
COMP. \_\_\_\_\_ CHECK \_\_\_\_\_ CONT. NO. \_\_\_\_\_



SCALE

HOR 1" = 10'

VER 1" = 10'

Station at DAM = 0+0

APPENDIX E  
INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS



# INVENTORY OF DAMS IN THE UNITED STATES

|       |          |        |      |                   |             |                  |                  |     |    |    |   |
|-------|----------|--------|------|-------------------|-------------|------------------|------------------|-----|----|----|---|
| ①     | ②        | ③      | ④    | ⑤                 | ⑥           | ⑦                | ⑧                | ⑨   | ⑩  | ⑪  | ⑫ |
| STATE | DIVISION | COUNTY | CITY | NAME              | REPORT DATE | LATITUDE (NORTH) | LONGITUDE (WEST) | DAY | MO | YR |   |
| CT    | 520      | NEU    | 02   | COLUMBIA LAKE DAM | 15 AUG 78   | 4143.3           | 7220.0           |     |    |    |   |

|              |                    |
|--------------|--------------------|
| POPULAR NAME | NAME OF IMPONDMENT |
|              | COLUMBIA LAKE      |

|              |                     |                                      |                     |            |
|--------------|---------------------|--------------------------------------|---------------------|------------|
| REGION BASIN | RIVER OR STREAM     | NEAREST DOWNSTREAM CITY-TOWN-VILLAGE | DIST FROM DAM (MI.) | POPULATION |
| 01 07        | COLUMBIA LAKE BROOK | HOP RIVER                            | 1                   | 1000       |

|             |                |          |                     |                        |                                  |                       |       |       |       |           |
|-------------|----------------|----------|---------------------|------------------------|----------------------------------|-----------------------|-------|-------|-------|-----------|
| TYPE OF DAM | YEAR COMPLETED | PURPOSES | STATIC HEIGHT (FT.) | HYDRAULIC HEIGHT (FT.) | IMPOUNDING CAPACITIES (ACRE-FT.) | DIST DOWN RIVER (MI.) | FED N | PRV N | SCS A | VER/DATE  |
| WEPG        | 1965           | R        | 24                  | 27                     | 4450                             | 5570                  | N     | N     | N     | 07 AUG 78 |

|          |          |                         |                    |                     |           |          |           |                  |              |             |             |
|----------|----------|-------------------------|--------------------|---------------------|-----------|----------|-----------|------------------|--------------|-------------|-------------|
| REMARKS  |          |                         |                    |                     |           |          |           |                  |              |             |             |
| DIS. HAS | SHILLWAY | MAXIMUM DISCHARGE (FT.) | VOLUME OF DAM (CV) | POWER CAPACITY (MW) | INSTALLED | PROPOSED | NO. LOCKS | NAVIGATION LOCKS | LENGTH (FT.) | WIDTH (FT.) | DEPTH (FT.) |
| 2        | 245      | 020                     |                    |                     |           |          |           |                  |              |             |             |

|                  |                |                 |
|------------------|----------------|-----------------|
| OWNER            | ENGINEERING BY | CONSTRUCTION BY |
| TOWN OF COLUMBIA | UNKNOWN        | UNKNOWN         |

|        |              |           |             |
|--------|--------------|-----------|-------------|
| DESIGN | CONSTRUCTION | OPERATION | MAINTENANCE |
|        |              |           |             |

|                  |                 |     |    |    |    |        |                          |
|------------------|-----------------|-----|----|----|----|--------|--------------------------|
| INSPECTION BY    | INSPECTION DATE | DAY | MO | YR | PL | 92-367 | AUTHORITY FOR INSPECTION |
| Coe Maguire Inc. | 18 MAY 78       |     |    |    |    |        |                          |

|         |  |
|---------|--|
| REMARKS |  |
|         |  |

ATE  
LMED  
-8